

Summary by Subtotal

Vendor: TARGET

Labor Level: CONEST

18 May 2016 10:42:44

Subtotal 2 - EMT

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
10054	3/4	EMT	M	200	FT	0.5131	102.61	0.0265	5.30	0.0000	0.00
10054	3/4	EMT	M	250	FT	0.5131	128.27	0.0275	6.87	0.0000	0.00
10054	3/4	EMT	M	210	FT	0.5131	107.75	0.0291	6.11	0.0000	0.00
10054	3/4	EMT	M	84	FT	0.5131	43.10	0.0297	2.49	0.0000	0.00
10054	3/4	EMT	M	260	FT	0.5131	133.40	0.0330	8.58	0.0000	0.00
10054	3/4	EMT	M	25	FT	0.5131	12.83	0.0388	0.97	0.0000	0.00
10055	1	EMT	M	140	FT	0.8549	119.68	0.0304	4.26	0.0000	0.00
10055	1	EMT	M	120	FT	0.8549	102.58	0.0387	4.64	0.0000	0.00
10055	1	EMT	M	15	FT	0.8549	12.82	0.0473	0.71	0.0000	0.00
10056	1 1/4	EMT	M	15	FT	1.3488	20.23	0.0451	0.68	0.0000	0.00
10057	1 1/2	EMT	M	15	FT	1.6786	25.18	0.0503	0.75	0.0000	0.00
10058	2	EMT	M	15	FT	1.9911	29.87	0.0580	0.87	0.0000	0.00
10059	2 1/2	EMT	M	15	FT	2.9494	44.24	0.0683	1.02	0.0000	0.00

Subtotal totals: 882.56 43.26 0.00

Subtotal 10 - RIGID FITTINGS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
40126	1	GRND BUSHING INSULATED	M	2	EA	5.8776	11.76	0.3300	0.66	0.0000	0.00
40129	2	GRND BUSHING INSULATED	M	2	EA	11.5472	23.09	0.3960	0.79	0.0000	0.00
40176	3/4	PLASTIC BUSHING	M	14	EA	0.2954	4.14	0.0424	0.59	0.0000	0.00
40176	3/4	PLASTIC BUSHING	M	2	EA	0.2954	0.59	0.0440	0.09	0.0000	0.00
40176	3/4	PLASTIC BUSHING	M	4	EA	0.2954	1.18	0.0528	0.21	0.0000	0.00
40177	1	PLASTIC BUSHING	M	28	EA	0.4477	12.54	0.0422	1.18	0.0000	0.00
40177	1	PLASTIC BUSHING	M	2	EA	0.4477	0.90	0.0528	0.11	0.0000	0.00
40178	1 1/4	PLASTIC BUSHING	M	2	EA	0.6594	1.32	0.0660	0.13	0.0000	0.00
40179	1 1/2	PLASTIC BUSHING	M	2	EA	0.8901	1.78	0.0660	0.13	0.0000	0.00
40180	2	PLASTIC BUSHING	M	2	EA	1.6474	3.29	0.0660	0.13	0.0000	0.00
40181	2 1/2	PLASTIC BUSHING	M	2	EA	3.7090	7.42	0.0792	0.16	0.0000	0.00

Subtotal totals: 68.00 4.19 0.00

Subtotal 11 - EMT FITTINGS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
20737	3/4	EMT FIELD BEND	M	28	EA	0.0000	0.00	0.1060	2.97	0.0000	0.00
20737	3/4	EMT FIELD BEND	M	94	EA	0.0000	0.00	0.1100	10.34	0.0000	0.00
20737	3/4	EMT FIELD BEND	M	4	EA	0.0000	0.00	0.1320	0.53	0.0000	0.00
20738	1	EMT FIELD BEND	M	20	EA	0.0000	0.00	0.1650	3.30	0.0000	0.00
20749	1 1/4	EMT 90-ELBOW	M	3	EA	2.7552	8.27	0.3094	0.93	0.0000	0.00
20750	1 1/2	EMT 90-ELBOW	M	3	EA	3.2046	9.61	0.3867	1.16	0.0000	0.00
20751	2	EMT 90-ELBOW	M	2	EA	4.7082	9.42	0.4834	0.97	0.0000	0.00
20752	2 1/2	EMT 90-ELBOW	M	3	EA	10.8444	32.53	0.5800	1.74	0.0000	0.00
30285	3/4	EMT STEEL-SS COUPLING	M	20	EA	1.0750	21.50	0.0189	0.38	0.0000	0.00
30285	3/4	EMT STEEL-SS COUPLING	M	21	EA	1.0750	22.58	0.0208	0.44	0.0000	0.00
30285	3/4	EMT STEEL-SS COUPLING	M	9	EA	1.0750	9.68	0.0212	0.19	0.0000	0.00

Rav Estimating

Po Box 245
Marlboro, NY 12542

Phone: 845-236-7356

Web:

Subtotal 11 - EMT FITTINGS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
30285	3/4	EMT STEEL-SS COUPLING	M	24	EA	1.0750	25.80	0.0231	0.55	0.0000	0.00
30285	3/4	EMT STEEL-SS COUPLING	M	27	EA	1.0750	29.03	0.0277	0.75	0.0000	0.00
30286	1	EMT STEEL-SS COUPLING	M	14	EA	1.6034	22.45	0.0236	0.33	0.0000	0.00
30286	1	EMT STEEL-SS COUPLING	M	12	EA	1.6034	19.24	0.0299	0.36	0.0000	0.00
30286	1	EMT STEEL-SS COUPLING	M	2	EA	1.6034	3.21	0.0366	0.07	0.0000	0.00
30287	1 1/4	EMT STEEL-SS COUPLING	M	5	EA	3.1676	15.84	0.0516	0.26	0.0000	0.00
30288	1 1/2	EMT STEEL-SS COUPLING	M	5	EA	4.8648	24.32	0.0722	0.36	0.0000	0.00
30289	2	EMT STEEL-SS COUPLING	M	4	EA	6.3732	25.49	0.1031	0.41	0.0000	0.00
30290	2 1/2	EMT STEEL-SS COUPLING	M	5	EA	13.1611	65.81	0.1547	0.77	0.0000	0.00
30401	3/4	EMT STEEL SS CONNECTOR	M	44	EA	0.9148	40.25	0.0477	2.10	0.0000	0.00
30401	3/4	EMT STEEL SS CONNECTOR	M	22	EA	0.9148	20.12	0.0495	1.09	0.0000	0.00
30401	3/4	EMT STEEL SS CONNECTOR	M	4	EA	0.9148	3.66	0.0594	0.24	0.0000	0.00
30402	1	EMT STEEL SS CONNECTOR	M	28	EA	1.5071	42.20	0.0480	1.35	0.0000	0.00
30402	1	EMT STEEL SS CONNECTOR	M	18	EA	1.5071	27.13	0.0601	1.08	0.0000	0.00
30403	1 1/4	EMT STEEL SS CONNECTOR	M	2	EA	2.8268	5.65	0.0845	0.17	0.0000	0.00
30404	1 1/2	EMT STEEL SS CONNECTOR	M	2	EA	3.7335	7.47	0.0950	0.19	0.0000	0.00
30405	2	EMT STEEL SS CONNECTOR	M	2	EA	5.6190	11.24	0.1267	0.25	0.0000	0.00
30406	2 1/2	EMT STEEL SS CONNECTOR	M	2	EA	16.0270	32.05	0.1690	0.34	0.0000	0.00
161478	3/4	EMT 1-HOLE STEEL STRAP	M	3	EA	0.3843	1.15	0.0416	0.12	0.0000	0.00

Subtotal totals:

535.69

33.73

0.00

Subtotal 13 - HANGERS/SUPPORTS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
160229	1/4 x 3/4"	PLTD WEDGE ANCHOR	M	4	EA	0.3374	1.35	0.1386	0.55	0.0000	0.00
160230	1/4 x 2 1/4"	PLTD WEDGE ANCHOR	M	4	EA	0.4074	1.63	0.1320	0.53	0.0000	0.00
160230	1/4 x 2 1/4"	PLTD WEDGE ANCHOR	M	3	EA	0.4074	1.22	0.1386	0.42	0.0000	0.00
160351	1/4"	PLTD FLAT WASHER	M	440	EA	0.0188	8.28	0.0009	0.41	0.0000	0.00
160351	1/4"	PLTD FLAT WASHER	M	33	EA	0.0188	0.62	0.0012	0.04	0.0000	0.00
160351	1/4"	PLTD FLAT WASHER	M	160	EA	0.0188	3.01	0.0012	0.19	0.0000	0.00
160351	1/4"	PLTD FLAT WASHER	M	31	EA	0.0188	0.58	0.0014	0.04	0.0000	0.00
160352	5/16"	PLTD FLAT WASHER	M	9	EA	0.0461	0.42	0.0014	0.01	0.0000	0.00
160353	3/8"	PLTD FLAT WASHER	M	16	EA	0.0462	0.74	0.0013	0.02	0.0000	0.00
160353	3/8"	PLTD FLAT WASHER	M	18	EA	0.0462	0.83	0.0014	0.02	0.0000	0.00
160361	1/4"	PLTD LOCK WASHER	M	320	EA	0.0155	4.95	0.0009	0.30	0.0000	0.00
160361	1/4"	PLTD LOCK WASHER	M	160	EA	0.0155	2.47	0.0012	0.19	0.0000	0.00
160363	3/8"	PLTD LOCK WASHER	M	16	EA	0.0265	0.42	0.0013	0.02	0.0000	0.00
160363	3/8"	PLTD LOCK WASHER	M	18	EA	0.0265	0.48	0.0014	0.02	0.0000	0.00
160368	1/4 x 1"	PLTD FENDER WASHER	M	8	EA	0.0401	0.32	0.0011	0.01	0.0000	0.00
160509	3/8 x 1 1/2"	PLTD LAG BOLT	M	4	EA	0.1346	0.54	0.0396	0.16	0.0000	0.00
160509	3/8 x 1 1/2"	PLTD LAG BOLT	M	18	EA	0.1346	2.42	0.0416	0.75	0.0000	0.00
160684	3/8" LONG	LAG SHIELD	M	4	EA	0.7497	3.00	0.0660	0.26	0.0000	0.00
160684	3/8" LONG	LAG SHIELD	M	18	EA	0.7497	13.49	0.0693	1.25	0.0000	0.00
160724	1/4-20 x 1"	PLTD MACHINE SCREWS	M	8	EA	0.0206	0.16	0.0623	0.50	0.0000	0.00
160724	1/4-20 x 1"	PLTD MACHINE SCREWS	M	21	EA	0.0206	0.43	0.0647	1.36	0.0000	0.00
160724	1/4-20 x 1"	PLTD MACHINE SCREWS	M	12	EA	0.0206	0.25	0.0776	0.93	0.0000	0.00
160872	1/4-20	PLTD HEX NUTS	M	440	EA	0.0199	8.76	0.0185	8.13	0.0000	0.00
160872	1/4-20	PLTD HEX NUTS	M	96	EA	0.0199	1.91	0.0231	2.22	0.0000	0.00
160872	1/4-20	PLTD HEX NUTS	M	160	EA	0.0199	3.19	0.0236	3.77	0.0000	0.00
160872	1/4-20	PLTD HEX NUTS	M	64	EA	0.0199	1.27	0.0277	1.77	0.0000	0.00
160873	5/16-18	PLTD HEX NUTS	M	9	EA	0.0280	0.25	0.0305	0.27	0.0000	0.00
160874	3/8-16	PLTD HEX NUTS	M	12	EA	0.0578	0.69	0.0396	0.48	0.0000	0.00
161084	#10 x 1"	TEK SCREW	M	257	EA	0.0218	5.59	0.0180	4.61	0.0000	0.00
161084	#10 x 1"	TEK SCREW	M	48	EA	0.0218	1.04	0.0180	0.86	0.0000	0.00
161084	#10 x 1"	TEK SCREW	M	123	EA	0.0218	2.68	0.0224	2.76	0.0000	0.00
161084	#10 x 1"	TEK SCREW	M	35	EA	0.0218	0.76	0.0236	0.82	0.0000	0.00
161087	1/4"	SELF DRILLING THREADED ANCHOR	M	21	EA	0.2580	5.42	0.1155	2.43	0.0000	0.00
161087	1/4"	SELF DRILLING THREADED ANCHOR	M	12	EA	0.2580	3.10	0.1386	1.66	0.0000	0.00

Subtotal 13 - HANGERS/SUPPORTS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
161093	#12 x 1"	SHEET METAL SCREW	M	3	EA	0.0590	0.18	0.0243	0.07	0.0000	0.00
161122	#12 x 1 1/4"	PLASTIC ANCHOR	M	3	EA	0.0204	0.06	0.0347	0.10	0.0000	0.00
161125	3/16 x 1 1/2 - 3"	HAMMER DRILLED HOLE	M	3	EA	0.0000	0.00	0.2218	0.67	0.0000	0.00
161126	1/4 x 1 1/2 - 3"	HAMMER DRILLED HOLE	M	7	EA	0.0000	0.00	0.2495	1.75	0.0000	0.00
161127	3/8 x 1 1/2 - 3"	HAMMER DRILLED HOLE	M	4	EA	0.0000	0.00	0.2640	1.06	0.0000	0.00
161127	3/8 x 1 1/2 - 3"	HAMMER DRILLED HOLE	M	18	EA	0.0000	0.00	0.2772	4.99	0.0000	0.00
161151	7"	TIE-WRAP	M	152	EA	0.0944	14.34	0.0208	3.16	0.0000	0.00
161151	7"	TIE-WRAP	M	84	EA	0.0944	7.93	0.0277	2.33	0.0000	0.00
161171	1/4-20	THREADED ROD	M	118	FT	0.2856	33.70	0.0462	5.45	0.0000	0.00
161171	1/4-20	THREADED ROD	M	4	FT	0.2856	1.14	0.0578	0.23	0.0000	0.00
161171	1/4-20	THREADED ROD	M	46	FT	0.2856	13.14	0.0589	2.71	0.0000	0.00
161171	1/4-20	THREADED ROD	M	-21	FT	0.2856	-6.00	0.0693	-1.46	0.0000	0.00
161173	3/8-16	THREADED ROD	M	26	FT	0.5173	13.45	0.0660	1.72	0.0000	0.00
161286	24"	T-BAR BOX HANGER	M	1	EA	2.4523	2.45	0.0334	0.03	0.0000	0.00
161286	24"	T-BAR BOX HANGER	M	6	EA	2.4523	14.71	0.0416	0.25	0.0000	0.00
161571	4"x 4"x .04 57psi	POLYURETHANE PAD	M	4	EA	0.0000	0.00	0.0660	0.26	0.0000	0.00
240110	1 5/8" x 13/16"H	P4000 16G STRUT SOLID GREEN	M	4	FT	2.2411	8.96	0.1056	0.42	0.0000	0.00
240135	1 5/8" x 13/16"H	P4100 14G STRUT 1-1/8"SLOT GREEN	M	18	FT	2.7389	49.30	0.1109	2.00	0.0000	0.00
240365	3/8 -16EG	U-STRUT SPRING NUT (1 5/8H)	M	4	EA	0.9354	3.74	0.0594	0.24	0.0000	0.00
630000	1/2	CONDUIT HGR SNAP-CLOSE 9/32 HOLE-MTD HD	M	21	EA	0.1809	3.80	0.0312	0.65	0.0000	0.00
630001	3/4	CONDUIT HGR SNAP-CLOSE 9/32 HOLE-MTD HD	M	80	EA	0.1590	12.72	0.0296	2.37	0.0000	0.00
630001	3/4	CONDUIT HGR SNAP-CLOSE 9/32 HOLE-MTD HD	M	40	EA	0.1590	6.36	0.0377	1.51	0.0000	0.00
630002	1	CONDUIT HGR SNAP-CLOSE 9/32 HOLE-MTD HD	M	12	EA	0.2156	2.59	0.0437	0.52	0.0000	0.00
630033	1	EMT HGR NUT-BOLT CLOSE 1/4 HOLE-MTD	M	3	EA	0.2986	0.90	0.0485	0.15	0.0000	0.00
630053	1/2 3/4 or AC/MC	EMT SCREW-ON SUPPORT (USE W/2-1/8D BOX)	M	4	EA	0.2192	0.88	0.0422	0.17	0.0000	0.00
630062	3/4	COND SNP-CLOSE HGR TO SCRW-ON STUD-WALL	M	17	EA	0.4758	8.09	0.0339	0.58	0.0000	0.00
630063	1	COND SNP-CLOSE HGR TO SCRW-ON STUD-WALL	M	28	EA	0.5297	14.83	0.0370	1.03	0.0000	0.00
630190	1 1/4	COND 1-PC w/BOLT STL U-STRUT CLMP	M	3	EA	0.5011	1.50	0.0554	0.17	0.0000	0.00
630191	1 1/2	COND 1-PC w/BOLT STL U-STRUT CLMP	M	3	EA	0.6198	1.86	0.0624	0.19	0.0000	0.00
630192	2	COND 1-PC w/BOLT STL U-STRUT CLMP	M	3	EA	0.6592	1.98	0.0693	0.21	0.0000	0.00
630193	2 1/2	COND 1-PC w/BOLT STL U-STRUT CLMP	M	3	EA	0.9403	2.82	0.0762	0.23	0.0000	0.00
630260	3/4	EMT BOT-MOUNT BOLT-IN CLAMP 5/8-BEAM	M	24	EA	0.8429	20.23	0.0303	0.73	0.0000	0.00
630328	14-2>10-3 & 3/8	MC/AC/FLEX HGR PUSH-IN MTL/WOOD/STUD	M	104	EA	0.1819	18.92	0.0422	4.39	0.0000	0.00
630328	14-2>10-3 & 3/8	MC/AC/FLEX HGR PUSH-IN MTL/WOOD/STUD	M	17	EA	0.1819	3.09	0.0444	0.75	0.0000	0.00
630362	14>10-3 (2-CBL)	AC/MC HMR-ON BOT-MTD 1/4-FLNG HGR PSH-IN	M	219	EA	0.5443	119.21	0.0444	9.71	0.0000	0.00
630484	3/8 PLAIN/THREAD ROD	COMB BOX & 1/2 > 3/4" SNP-CLS COND HGR	M	8	EA	1.8228	14.58	0.0334	0.27	0.0000	0.00
630488	THREAD ROD MOUNT	COMB BOX & 1/2 > 3/4" SNP-CLS COND HGR	M	30	EA	1.5897	47.69	0.0277	0.83	0.0000	0.00
630488	THREAD ROD MOUNT	COMB BOX & 1/2 > 3/4" SNP-CLS COND HGR	M	3	EA	1.5897	4.77	0.0347	0.10	0.0000	0.00
630488	THREAD ROD MOUNT	COMB BOX & 1/2 > 3/4" SNP-CLS COND HGR	M	4	EA	1.5897	6.36	0.0416	0.17	0.0000	0.00
630526	1/4-20	WASHER NUT 1/4-20	M	1	EA	0.1010	0.10	0.0277	0.03	0.0000	0.00
630540	1/4"FLANGE	HAMMER-ON CLIP -1/4>3/8 NUTS REQUIRED	M	30	EA	0.4867	14.60	0.0277	0.83	0.0000	0.00
630540	1/4"FLANGE	HAMMER-ON CLIP -1/4>3/8 NUTS REQUIRED	M	160	EA	0.4867	77.87	0.0295	4.71	0.0000	0.00
630540	1/4"FLANGE	HAMMER-ON CLIP -1/4>3/8 NUTS REQUIRED	M	3	EA	0.4867	1.46	0.0347	0.10	0.0000	0.00
630540	1/4"FLANGE	HAMMER-ON CLIP -1/4>3/8 NUTS REQUIRED	M	160	EA	0.4867	77.87	0.0353	5.65	0.0000	0.00
630557	1/4" FLANGE	HAMMER-ON FLANGE CLIP - 1/4-20 x 3/8 STD	M	1	EA	0.3707	0.37	0.0416	0.04	0.0000	0.00
630567	1/4-20	ADJ BEAM CLAMP UP TO 1/2 FLANGE	M	8	EA	0.3962	3.17	0.0557	0.45	0.0000	0.00
630641	3/8 THREAD-ROD	ANGLE BRKT SUPT-HOLE MTD	M	4	EA	0.3736	1.49	0.0528	0.21	0.0000	0.00
630642	1/4-3/8" THRD ROD	ANGLE BRKT SUPT-HOLE MTD	M	21	EA	0.3450	7.25	0.0462	0.97	0.0000	0.00
630642	1/4-3/8" THRD ROD	ANGLE BRKT SUPT-HOLE MTD	M	19	EA	0.3450	6.56	0.0554	1.05	0.0000	0.00
630690	1/4-20 x 5/8" STUD	T-BAR/ INDEPENDENT SUPT HGR	M	63	EA	0.4846	30.53	0.1109	6.99	0.0000	0.00

Subtotal totals: 753.84 109.51 0.00

Subtotal 14 - FLEXIBLE CONDUIT

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
50003	1	FLEXIBLE STEEL CONDUIT	M	3	FT	1.0905	3.27	0.0693	0.21	0.0000	0.00
50006	2	FLEXIBLE STEEL CONDUIT	M	3	FT	2.8079	8.42	0.1848	0.55	0.0000	0.00
50019	1/2	FLEXIBLE ALUM CONDUIT	M	10	FT	0.4787	4.79	0.0277	0.28	0.0000	0.00

Rav Estimating

Po Box 245
Marlboro, NY 12542

Phone: 845-236-7356
Web:

Subtotal 14 - FLEXIBLE CONDUIT

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
50019	1/2	FLEXIBLE ALUM CONDUIT	M	18	FT	0.4787	8.62	0.0333	0.60	0.0000	0.00
Subtotal totals:						25.10		1.64		0.00	

Subtotal 17 - GROUNDING

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
850177		CADWELD & CLEAN	M	2	EA	9.2400	18.48	0.9000	1.80	0.0000	0.00
Subtotal totals:						18.48		1.80		0.00	

Subtotal 18 - FIXTURES

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
120594		CEILING TILE CUT OUT	M	1	EA	0.0000	0.00	0.0890	0.09	0.0000	0.00
120784	2 x 2	LED T-BAR LAY-IN FIXTURE	M	6	EA	0.0000	0.00	0.5821	3.49	0.0000	0.00
120793	48" LONG	LED SURFACE FIXTURE W/LENS	M	3	EA	0.0000	0.00	0.8732	2.62	0.0000	0.00
120795	96" LONG	LED SURFACE FIXTURE W/LENS	M	19	EA	0.0000	0.00	1.1157	21.20	0.0000	0.00
120802		LED RECESSED RND FIXTURE-LABOR	M	12	EA	0.0000	0.00	1.2128	14.55	0.0000	0.00
120819		EXIT PENDANT MTD 2-FACE	M	5	EA	0.0000	0.00	0.8177	4.09	0.0000	0.00
Subtotal totals:						0.00		46.04		0.00	

Subtotal 19 - LAMPS & BALLASTS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
830976	ELECTRONIC	EMERGENCY BALLAST FIELD INST LBR	M	5	EA	0.0000	0.00	0.3300	1.65	0.0000	0.00
Subtotal totals:						0.00		1.65		0.00	

Subtotal 20 - SUPPORTS FIXTURE

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
121182	515A	LAY-IN T-BAR CLIP UPTURNED LIP	M	24	EA	0.1740	4.18	0.0416	1.00	0.0000	0.00
121186		DROP WIRE (COLORED)	M	661	FT	0.0000	0.00	0.0139	9.16	0.0000	0.00
121206		ADJ FIXTURE T-BAR HANGER SET	M	24	EA	2.0538	49.29	0.0832	2.00	0.0000	0.00
Subtotal totals:						53.47		12.16		0.00	

Subtotal 21 - DEVICES

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
140016	20A	DX RECEPT SPECIFICATION GRADE	M	18	EA	9.1344	164.42	0.1901	3.42	0.0000	0.00
140016	20A	DX RECEPT SPECIFICATION GRADE	M	18	EA	9.1344	164.42	0.2376	4.28	0.0000	0.00
140024	20A	DUPLEX GFCI RECEPTACLE	M	1	EA	7.5012	7.50	0.2904	0.29	0.0000	0.00
140035	20A 2P3W	SGL RECEPT 125V N5-20R SPEC- GRADE	M	8	EA	5.9567	47.65	0.2376	1.90	0.0000	0.00
140393	20A	1P TOGGLE SPECIFICATION -GRADE	M	2	EA	7.7661	15.53	0.2376	0.48	0.0000	0.00
140517	ODS0D-IDI	OCCUPANCY SENSOR SW DUAL-RELAY PIR 800W	M	13	EA	39.5640	514.33	0.2640	3.43	0.0000	0.00
140520	CI-355	PIR OCCUPANCY SENSOR CEILING MTD 1200SF	M	1	EA	38.6400	38.64	0.3465	0.35	0.0000	0.00
Subtotal totals:						952.50		14.14		0.00	

Subtotal 22 - PLATES

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
140634	2-TOGGLE	2G STAINLESS STEEL PLATE	M	1	EA	1.8782	1.88	0.0792	0.08	0.0000	0.00
140642	1-DUPLEX	1G STAINLESS STEEL PLATE	M	18	EA	0.9390	16.90	0.0528	0.95	0.0000	0.00
140643	2-DUPLEX	2G STAINLESS STEEL PLATE	M	9	EA	1.8782	16.90	0.0792	0.71	0.0000	0.00
140647	1-DECORA	1G STAINLESS STEEL PLATE	M	13	EA	0.9390	12.21	0.0528	0.69	0.0000	0.00
140647	1-DECORA	1G STAINLESS STEEL PLATE	M	1	EA	0.9390	0.94	0.0660	0.07	0.0000	0.00
140665	15>20A 1.4 DIA HOLE	1G S-STL SGL RECEPT PLATE	M	8	EA	0.9390	7.51	0.0660	0.53	0.0000	0.00
Subtotal totals:						56.34		3.02		0.00	

Subtotal 23 - STEEL BOXES

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
--------	------	-------------	-----	----------	-----	----------	------------	----------	------------	----------	------------

Rav Estimating

Po Box 245
Marlboro, NY 12542

Phone: 845-236-7356
Web:

Subtotal 23 - STEEL BOXES

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
150006	1-1/2"D	4"SQ CMB- KO NO BRKT	M	20	EA	2.0000	40.00	0.1109	2.22	0.0000	0.00
150006	1-1/2"D	4"SQ CMB- KO NO BRKT	M	8	EA	2.0000	16.00	0.1336	1.07	0.0000	0.00
150006	1-1/2"D	4"SQ CMB- KO NO BRKT	M	3	EA	2.0000	6.00	0.1386	0.42	0.0000	0.00
150006	1-1/2"D	4"SQ CMB- KO NO BRKT	M	1	EA	2.0000	2.00	0.1663	0.17	0.0000	0.00
150014	1-1/2"D	4"SQ CMB- KO FH- BRKT	M	7	EA	3.5000	24.50	0.1272	0.89	0.0000	0.00
150015	1-1/2"D	4"SQ CMB- KO FM- BRKT	M	18	EA	3.5000	63.00	0.1267	2.28	0.0000	0.00
150015	1-1/2"D	4"SQ CMB- KO FM- BRKT	M	17	EA	3.5000	59.50	0.1584	2.69	0.0000	0.00
150018	1-1/2"D	4"SQ 3/4"- KO FM - BRKT	M	13	EA	3.5000	45.50	0.1267	1.65	0.0000	0.00
150042	2-1/8"D	4"SQ 1"-KO NO BRKT	M	14	EA	3.5000	49.00	0.1267	1.77	0.0000	0.00
150045	2-1/8"D	4"SQ CMB- KO TS- BRKT	M	1	EA	1.0458	1.05	0.1584	0.16	0.0000	0.00
150046	2-1/8"D	4"SQ CMB- KO FM- BRKT	M	1	EA	3.5000	3.50	0.1584	0.16	0.0000	0.00
150061	5/8"RISE 4.8-CI	1G 4"SQ PLASTER-RING	M	31	EA	2.6792	83.06	0.0528	1.64	0.0000	0.00
150061	5/8"RISE 4.8-CI	1G 4"SQ PLASTER-RING	M	7	EA	2.6792	18.75	0.0530	0.37	0.0000	0.00
150061	5/8"RISE 4.8-CI	1G 4"SQ PLASTER-RING	M	9	EA	2.6792	24.11	0.0660	0.59	0.0000	0.00
150070	5/8"RISE 7.5-CI	2G 4"SQ PLASTER-RING	M	14	EA	3.5757	50.06	0.0528	0.74	0.0000	0.00
150070	5/8"RISE 7.5-CI	2G 4"SQ PLASTER-RING	M	10	EA	3.5757	35.76	0.0660	0.66	0.0000	0.00
150091		4"SQ BLANK CVR	M	20	EA	1.5610	31.22	0.0277	0.55	0.0000	0.00
150091		4"SQ BLANK CVR	M	8	EA	1.5610	12.49	0.0334	0.27	0.0000	0.00
150091		4"SQ BLANK CVR	M	3	EA	1.5610	4.68	0.0346	0.10	0.0000	0.00
150091		4"SQ BLANK CVR	M	1	EA	1.5610	1.56	0.0416	0.04	0.0000	0.00
150128	1-1/2 D 29.5-CI	4-11/16" BOX /NO BRKT COMB KO	M	10	EA	5.0000	50.00	0.1109	1.11	0.0000	0.00
150128	1-1/2 D 29.5-CI	4-11/16" BOX /NO BRKT COMB KO	M	4	EA	4.0000	16.00	0.1663	0.67	0.0000	0.00
150162		4-11/16" BLANK CVR	M	10	EA	1.3555	13.55	0.0277	0.28	0.0000	0.00
150162		4-11/16" BLANK CVR	M	4	EA	1.3555	5.42	0.0416	0.17	0.0000	0.00
150191	1-1/2"D 15.5-CI	4" OCTAGON 1/2" KO	M	5	EA	2.0000	10.00	0.1109	0.55	0.0000	0.00
150193	1-1/2"D 15.5-CI	4" OCTAGON COMB KO	M	1	EA	2.0000	2.00	0.0890	0.09	0.0000	0.00
150205	1-1/2"D 15.5-CI	4" OCTAGON BX CLAMPS	M	1	EA	2.0000	2.00	0.1109	0.11	0.0000	0.00
Subtotal totals:						670.71		21.41		0.00	

Subtotal 26 - FLOOR BOXES

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
150979	PWR+2-LV KO WJB	POKE THRU/FLUSH FIRE RATED 2-PIECE-MULTI	M	5	EA	126.0000	630.00	1.4520	7.26	0.0000	0.00
Subtotal totals:						630.00		7.26		0.00	

Subtotal 29 - MISC WIRE/TECK CABLE

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
90240	#14 2/C Red	FA CABLE PLENUM SHIELD (FPLP)	M	200	FT	0.7600	152.00	0.0100	2.00	0.0000	0.00
90241	#14 4/C Red	FA CABLE PLENUM SHIELD (FPLP)	M	200	FT	0.8500	170.00	0.0120	2.40	0.0000	0.00
90295	4 PAIR	CAT 5E CABLE-PLENUM	M	100	FT	0.2433	24.33	0.0035	0.35	0.0000	0.00
90346	16/4PR	CNTRL CBL SHLD TWSTD PR	M	150	FT	0.3500	52.50	0.0160	2.40	0.0000	0.00
500116		PULL LINE (STRING)	M	168	FT	0.0089	1.49	0.0021	0.35	0.0000	0.00
500116		PULL LINE (STRING)	M	101	FT	0.0089	0.89	0.0021	0.21	0.0000	0.00
Subtotal totals:						401.22		7.72		0.00	

Subtotal 31 - THHN/THWN CU

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
70033	12	THHN/THWN CU (STR)	M	1,453	FT	0.1173	170.49	0.0022	3.26	0.0000	0.00
70033	12	THHN/THWN CU (STR)	M	1,375	FT	0.1173	161.34	0.0026	3.51	0.0000	0.00
70033	12	THHN/THWN CU (STR)	M	2,003	FT	0.1173	235.03	0.0026	5.19	0.0000	0.00
70033	12	THHN/THWN CU (STR)	M	364	FT	0.1173	42.71	0.0033	1.21	0.0000	0.00
70033	12	THHN/THWN CU (STR)	M	216	FT	0.1173	25.35	0.0044	0.96	0.0000	0.00
70035	8	THHN/THWN CU (STR)	M	54	FT	0.2895	15.64	0.0083	0.45	0.0000	0.00
70036	6.	THHN/THWN CU (STR)	M	12	FT	0.4950	5.94	0.0077	0.09	0.0000	0.00
70036	6.	THHN/THWN CU (STR)	M	90	FT	0.4950	44.55	0.0081	0.73	0.0000	0.00
70037	4.	THHN/THWN CU (STR)	M	60	FT	0.7652	45.91	0.0091	0.55	0.0000	0.00
70037	4.	THHN/THWN CU (STR)	M	27	FT	0.7652	20.66	0.0120	0.32	0.0000	0.00

Rav Estimating

Po Box 245
Marlboro, NY 12542

Phone: 845-236-7356
Web:

Subtotal 31 - THHN/THWN CU

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
70038	3.	THHN/THWN CU (STR)	M	120	FT	0.9585	115.02	0.0090	1.08	0.0000	0.00
70039	2.	THHN/THWN CU (STR)	M	90	FT	1.1998	107.98	0.0126	1.13	0.0000	0.00
70041	1/0	THHN/THWN CU (STR)	M	120	FT	1.8433	221.20	0.0132	1.59	0.0000	0.00
70043	3/0	THHN/THWN CU (STR)	M	36	FT	2.8988	104.36	0.0240	0.86	0.0000	0.00
70044	4/0	THHN/THWN CU (STR)	M	120	FT	3.6401	436.82	0.0173	2.08	0.0000	0.00
Subtotal totals:						1,753.00	23.02			0.00	0.00

Subtotal 33 - BARE & GREEN WIRE

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
70145	12.	GREEN THHN CU (GRD 20A)	M	132	FT	0.1173	15.49	0.0022	0.30	0.0000	0.00
70145	12.	GREEN THHN CU (GRD 20A)	M	275	FT	0.1173	32.27	0.0026	0.70	0.0000	0.00
70145	12.	GREEN THHN CU (GRD 20A)	M	286	FT	0.1173	33.56	0.0026	0.74	0.0000	0.00
70145	12.	GREEN THHN CU (GRD 20A)	M	122	FT	0.1173	14.32	0.0033	0.41	0.0000	0.00
70147	8	GREEN THHN CU (GRD 100A)	M	27	FT	0.2895	7.82	0.0067	0.18	0.0000	0.00
70147	8	GREEN THHN CU (GRD 100A)	M	9	FT	0.2895	2.61	0.0083	0.07	0.0000	0.00
70148	6.	GREEN THHN CU (GRD 200A)	M	57	FT	0.4950	28.21	0.0066	0.38	0.0000	0.00
70148	6.	GREEN THHN CU (GRD 200A)	M	30	FT	0.4950	14.85	0.0077	0.23	0.0000	0.00
70148	6.	GREEN THHN CU (GRD 200A)	M	9	FT	0.4950	4.45	0.0102	0.09	0.0000	0.00
70149	4.	GREEN THHN CU (GRD 300A)	M	30	FT	0.7652	22.96	0.0078	0.23	0.0000	0.00
Subtotal totals:						176.53	3.33			0.00	0.00

Subtotal 37 - ROMEX/BX/UF/MC

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
70313	12/2	MC CABLE - ALUM JKT W/G	M	15	FT	0.3616	5.42	0.0235	0.35	0.0000	0.00
70313	12/2	MC CABLE - ALUM JKT W/G	M	1,059	FT	0.3616	382.96	0.0252	26.71	0.0000	0.00
70325	10/2	MC CABLE - ALUM JKT W/G	M	100	FT	0.7597	75.97	0.0249	2.49	0.0000	0.00
Subtotal totals:						464.35	29.56			0.00	0.00

Subtotal 42 - WIRE TERMINATIONS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
100002	8	AL/CU CRIMP LUG 1-HOLE	M	1	EA	5.1328	5.13	0.1980	0.20	0.0000	0.00
100003	6.	AL/CU CRIMP LUG 1-HOLE	M	1	EA	6.4376	6.44	0.2640	0.26	0.0000	0.00
100004	4.	AL/CU CRIMP LUG 1-HOLE	M	3	EA	5.4151	16.25	0.3300	0.99	0.0000	0.00
100024	3/0	AL/CU CRIMP LUG 2-HOLE	M	4	EA	22.5669	90.27	0.5610	2.24	0.0000	0.00
100085	#18 to 10	WIRE-NUT SML -YELLOW	M	1	EA	0.0465	0.05	0.0485	0.05	0.0000	0.00
100086	#22 to 8	WIRE-NUT MED -TAN	M	3	EA	0.0532	0.16	0.0554	0.17	0.0000	0.00
100087	#18 to 8	WIRE-NUT MED - RED	M	90	EA	0.0605	5.44	0.0388	3.49	0.0000	0.00
100087	#18 to 8	WIRE-NUT MED - RED	M	24	EA	0.0605	1.45	0.0467	1.12	0.0000	0.00
100087	#18 to 8	WIRE-NUT MED - RED	M	9	EA	0.0605	0.54	0.0485	0.44	0.0000	0.00
100087	#18 to 8	WIRE-NUT MED - RED	M	14	EA	0.0605	0.85	0.0582	0.81	0.0000	0.00
100097	#12	PIGTAIL W/GRD SCREW	M	30	EA	0.2804	8.41	0.0388	1.16	0.0000	0.00
100097	#12	PIGTAIL W/GRD SCREW	M	31	EA	0.2804	8.69	0.0444	1.37	0.0000	0.00
100097	#12	PIGTAIL W/GRD SCREW	M	8	EA	0.2804	2.24	0.0467	0.37	0.0000	0.00
100097	#12	PIGTAIL W/GRD SCREW	M	3	EA	0.2804	0.84	0.0485	0.15	0.0000	0.00
100097	#12	PIGTAIL W/GRD SCREW	M	20	EA	0.2804	5.61	0.0554	1.11	0.0000	0.00
100097	#12	PIGTAIL W/GRD SCREW	M	9	EA	0.2804	2.52	0.0582	0.52	0.0000	0.00
100109	18-12	PSH-IN 2-WIRE CONN	M	45	EA	0.0448	2.02	0.0277	1.25	0.0000	0.00
100110	18-12	PSH-IN 3-WIRE CONN	M	31	EA	0.0483	1.50	0.0264	0.82	0.0000	0.00
100110	18-12	PSH-IN 3-WIRE CONN	M	11	EA	0.0483	0.53	0.0330	0.36	0.0000	0.00
100111	18-12	PSH-IN 4-WIRE CONN	M	9	EA	0.0518	0.47	0.0317	0.29	0.0000	0.00
100111	18-12	PSH-IN 4-WIRE CONN	M	7	EA	0.0518	0.36	0.0396	0.28	0.0000	0.00
100111	18-12	PSH-IN 4-WIRE CONN	M	135	EA	0.0518	6.99	0.0416	5.61	0.0000	0.00
100170	12	WIRE TERMINATION LBR	M	120	EA	0.0000	0.00	0.0257	3.09	0.0000	0.00
100170	12	WIRE TERMINATION LBR	M	48	EA	0.0000	0.00	0.0297	1.43	0.0000	0.00
100172	8	WIRE TERMINATION LBR	M	4	EA	0.0000	0.00	0.1320	0.53	0.0000	0.00
100173	6.	WIRE TERMINATION LBR	M	2	EA	0.0000	0.00	0.1584	0.32	0.0000	0.00

Subtotal 42 - WIRE TERMINATIONS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
100174	4.	WIRE TERMINATION LBR	M	2	EA	0.0000	0.00	0.1980	0.40	0.0000	0.00
100175	3.	WIRE TERMINATION LBR	M	8	EA	0.0000	0.00	0.2112	1.69	0.0000	0.00
100176	2.	WIRE TERMINATION LBR	M	6	EA	0.0000	0.00	0.2310	1.39	0.0000	0.00
100179	1/0	WIRE TERMINATION LBR	M	16	EA	0.0000	0.00	0.2442	3.91	0.0000	0.00
100182	4/0	WIRE TERMINATION LBR	M	8	EA	0.0000	0.00	0.2904	2.32	0.0000	0.00
100286	3/8-1/2	ANTI-SHORT	M	2	EA	0.0003	0.00	0.0133	0.03	0.0000	0.00
100286	3/8-1/2	ANTI-SHORT	M	2	EA	0.0003	0.00	0.0166	0.03	0.0000	0.00
100289	SIZE 2	ANTI-SHORT 12/4 10/2 10/3 2/1	M	2	EA	0.0957	0.19	0.0172	0.03	0.0000	0.00
670027	3/8	BX /MC 2-SCR SNGL STR-CONN	M	2	EA	0.5450	1.09	0.0854	0.17	0.0000	0.00
670027	3/8	BX /MC 2-SCR SNGL STR-CONN	M	1	EA	0.5450	0.54	0.1067	0.11	0.0000	0.00
670032	3/8	BX /MC 1-SCR SNGL STR-CONN	M	2	EA	0.7520	1.50	0.1016	0.20	0.0000	0.00
670064	3/8 (38AST)	AC/MC SNAP 2-IT INSUL	M	8	EA	0.3053	2.44	0.0520	0.42	0.0000	0.00
670064	3/8 (38AST)	AC/MC SNAP 2-IT INSUL	M	4	EA	0.3053	1.22	0.0528	0.21	0.0000	0.00
670064	3/8 (38AST)	AC/MC SNAP 2-IT INSUL	M	36	EA	0.3053	10.99	0.0660	2.38	0.0000	0.00
670064	3/8 (38AST)	AC/MC SNAP 2-IT INSUL	M	6	EA	0.3053	1.83	0.0693	0.42	0.0000	0.00
670080	3/8 (383810AST)	AC/MC DX SNAP 2-IT SCR-CLP INS	M	11	EA	0.8180	9.00	0.0693	0.76	0.0000	0.00
670085	3/8 (3838AST)	AC/MC DX SNAP 2-IT INSUL	M	69	EA	0.8180	56.44	0.0624	4.30	0.0000	0.00
670085	3/8 (3838AST)	AC/MC DX SNAP 2-IT INSUL	M	32	EA	0.8180	26.18	0.0634	2.03	0.0000	0.00
670085	3/8 (3838AST)	AC/MC DX SNAP 2-IT INSUL	M	2	EA	0.8180	1.64	0.0792	0.16	0.0000	0.00
670085	3/8 (3838AST)	AC/MC DX SNAP 2-IT INSUL	M	29	EA	0.8180	23.72	0.0832	2.41	0.0000	0.00
1050210	4.	WIRE TERMINATION	M	2	EA	0.0000	0.00	0.1500	0.30	0.0000	0.00
Subtotal totals:						303.54		52.09		0.00	

Subtotal 43 - SWITCHGEAR-PANELS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
170235	125A MLO 3PH4W	PNLBD W/BOLT-ON BKRS	M	2	EA	15.0000	30.00	2.5080	5.02	0.0000	0.00
170237	225A MLO 3PH4W	PNLBD W/BOLT-ON BKRS	M	2	EA	15.0000	30.00	5.0160	10.03	0.0000	0.00
Subtotal totals:						60.00		15.05		0.00	

Subtotal 45 - DRY TRANSFORMERS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
190017	45 KVA	3PH DRY XFMR FLOOR MTD	M	1	EA	150.0000	150.00	14.5200	14.52	0.0000	0.00
Subtotal totals:						150.00		14.52		0.00	

Subtotal 48 - MOTORS CONTROLS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
200298	SIZE 0 230V 2-POLE	N-1 PUSH-BUTTON MANUAL STARTER	M	3	EA	35.0000	105.00	1.3200	3.96	0.0000	0.00
Subtotal totals:						105.00		3.96		0.00	

Subtotal 49 - EQUIPMENT TERMS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
210010		ELECTRIC WATER HEATER CONNECTION	M	1	EA	15.0000	15.00	0.6600	0.66	0.0000	0.00
Subtotal totals:						15.00		0.66		0.00	

Subtotal 50 - DISCONNECTS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
220067	200/3	F/HD/600V N-1 SAFETY-SW	M	1	EA	15.0000	15.00	5.0820	5.08	0.0000	0.00
Subtotal totals:						15.00		5.08		0.00	

Subtotal 60 - FIRE ALARM

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
320065		FIRE ALARM ADDRESSABLE BASE	M	1	EA	4.2000	4.20	0.4400	0.44	0.0000	0.00
320066		FIRE ALARM ADDRESSABLE HEAD	M	1	EA	0.0000	0.00	0.1320	0.13	0.0000	0.00
320095		FIRE ALARM STROBE LIGHT	M	4	EA	4.2000	16.80	0.4538	1.82	0.0000	0.00

Rav Estimating

Po Box 245
Marlboro, NY 12542

Phone: 845-236-7356
Web:

Subtotal 60 - FIRE ALARM

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
320096		FIRE ALARM STROBE/SPEAKER	M	3	EA	4.2000	12.60	0.4840	1.45	0.0000	0.00
320118		FIRE ALARM ADDRESSABLE CONTROL RELAY	M	2	EA	5.0000	10.00	0.6600	1.32	0.0000	0.00
Subtotal totals:						43.60		5.16		0.00	

Subtotal 71 - DEMOLITION

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
380032	100A	REMOVE EXISTING PANEL	M	4	EA	0.0000	0.00	2.6400	10.56	0.0000	0.00
380033	200A	REMOVE EXISTING PANEL	M	1	EA	0.0000	0.00	4.6200	4.62	0.0000	0.00
380048	75 TO 100 KVA	REMOVE EXISTING TRANSFORMER	M	1	EA	0.0000	0.00	4.0000	4.00	0.0000	0.00
Subtotal totals:						0.00		19.18		0.00	

Subtotal 73 - FUSES

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
230052	150 AMP	K5 NON-CL 600V FUSE	M	3	EA	0.0000	0.00	0.0660	0.20	0.0000	0.00
Subtotal totals:						0.00		0.20		0.00	

Subtotal 86 - LIGHTING CONTROL SYS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
870370	BZ-50	OCCUPANCY SENSOR UNIVERSAL POWER PACK	M	1	EA	14.2800	14.28	0.2772	0.28	0.0000	0.00
Subtotal totals:						14.28		0.28		0.00	

Subtotal 99 - MISCELLANEOUS ITEMS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
1		LIGHTING CONTROL PANEL	M	1		25.0000	25.00	4.0000	4.00	0.0000	0.00
2		TIME CLOCK OVERRIDE SWITCH	M	1		75.0000	75.00	0.7500	0.75	0.0000	0.00
3		FLOOR PENETRATION AND SEAL	M	5		350.0000	1,750.00	2.0000	10.00	0.0000	0.00
4		FLOOR PENETRATIONS AND SEAL	M	3		60.0000	180.00	1.5000	4.50	0.0000	0.00
5		EMON DEMON	M	1		950.0000	950.00	6.0000	6.00	0.0000	0.00
6		REWIRE EXISTING CIRCUITS	M	1		100.0000	100.00	4.0000	4.00	0.0000	0.00
7		REMOVE EXISTING FEEDERS	M	1		0.0000	0.00	8.0000	8.00	0.0000	0.00
8		GROUND BUILDING STEEL	M	1		150.0000	150.00	4.0000	4.00	0.0000	0.00
9		REMOVE EXISTING METER	M	1		1.0000	1.00	1.0000	1.00	0.0000	0.00
10		TEMP LIGHT AND POWER	M	1		1,000.0000	1,000.00	0.0000	0.00	0.0000	0.00
14		TEST FA SYSTEM	M	1		0.0000	0.00	4.0000	4.00	0.0000	0.00
15		GROUND BAR DETAIL	M	1		175.0000	175.00	2.5000	2.50	0.0000	0.00
500158	1	ENCLOSURE HOLE PUNCH	M	1	EA	0.0000	0.00	0.4752	0.48	0.0000	0.00
500159	1 1/4	ENCLOSURE HOLE PUNCH	M	2	EA	0.0000	0.00	0.5280	1.06	0.0000	0.00
500160	1 1/2	ENCLOSURE HOLE PUNCH	M	4	EA	0.0000	0.00	0.5940	2.38	0.0000	0.00
500161	2	ENCLOSURE HOLE PUNCH	M	3	EA	0.0000	0.00	0.6600	1.98	0.0000	0.00
500162	2 1/2	ENCLOSURE HOLE PUNCH	M	2	EA	0.0000	0.00	0.7260	1.45	0.0000	0.00
Subtotal totals:						4,406.00		56.09		0.00	

Subtotal 112 - FLEX COND FITTINGS

Item #	Size	Description	Q/M	Quantity	U/M	Mat Unit	Mat Result	Lab Unit	Lab Result	Quo Unit	Quo Result
50030	1/2	FLEX COND ANGLE CONN	M	2	EA	3.1598	6.32	0.1109	0.22	0.0000	0.00
50030	1/2	FLEX COND ANGLE CONN	M	3	EA	3.1598	9.48	0.1331	0.40	0.0000	0.00
50032	1	FLEX COND ANGLE CONN	M	1	EA	8.5341	8.53	0.1885	0.19	0.0000	0.00
50035	2	FLEX COND ANGLE CONN	M	1	EA	28.9249	28.92	0.3326	0.33	0.0000	0.00
50041	1/2	FLEX COND STRAIGHT CONN	M	2	EA	0.5283	1.06	0.0924	0.18	0.0000	0.00
50041	1/2	FLEX COND STRAIGHT CONN	M	3	EA	0.5283	1.58	0.1109	0.33	0.0000	0.00
50043	1	FLEX COND STRAIGHT CONN	M	1	EA	1.9102	1.91	0.1571	0.16	0.0000	0.00
50046	2	FLEX COND STRAIGHT CONN	M	1	EA	8.4893	8.49	0.2772	0.28	0.0000	0.00
Subtotal totals:						66.30		2.09		0.00	

Job totals:

12,620.50

537.81

0.00

Summary Phases

Phase > SubPhase > Level > SubLevel > Area

FIXTURES

DEVICES

BRANCH

HVAC & MOTORS

FEEDERS

DISTRIBUTION EQUIPMENT

TEMPORARY WIRING

FIRE ALARM

RACEWAYS

GROUNDING & BONDING
